SHIMOGA DIVISION.

Dated 7th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 20th January 1930, for extending the Girls' School Buildings at Tirthahalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. or office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 180 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Girls' School Buildings at Tirthahalli in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for extending the Girls' School Building at Tirthahalli.

Sl. No.	Items of work.	Per	Quantity
1	Earthwork excavation and filling basement	C.yd.	33
2	Stone jelly concrete in mortar	C.ft.	260
3	Burnt size stone in mortar	„	1,068
4	Burnt brick in mortar	„	2,146
5	Burnt stone slabs dressed 6" thick	S.ft.	214
6	Flooring Cuddapah slabs over 8" concrete and cement pointing	Sqr.	1·57
7	Flooring with Mangalore pattern tiles over 3" concrete and cement pointing.	„	3·48
8	Teakwood panelled doors including hinges, bolts, etc., complete.	S.ft.	36
9	Teakwood windows with glazed shutters inside and panelled shutters outside with hinges, bolts, etc., complete.	„	72
10	Teakwood ventilators including glass pan, etc., complete ...	„	45
11	Teakwood work wrought and put up	C.ft.	51·48
12	Roofing with First Class Mangalore tiles on teak reepers ...	Sqr.	7·08
13	Ridge tiles set in mortar	R.ft.	24
14	Fixing the old ridge tiles set in mortar	„	28
15	Zinc sheet roofing over the verandah over jungle wood reepers including the joining the zinc sheets.	S.ft.	291
16	Ceiling planks over the joists including verandah reepers at joists.	„	168
17	Teakwood eve boards with painting	R.ft.	105
18	Plastering the walls in chunam	Sqr.	37·50
19	White and colour washing	„	37·50
20	Ornamental cornice of 8" including plastering		

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Guni Narasapur, Malalkatte, Registered No. 390, Shimoga Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities of Restoring Guni Narasapur, Malalkatte, Reg. No. 390 in Bhadravathi Hobli, Shimoga Taluk.

Sl. No.	Items of work	Per	Quantity
	Bund.		
1	Jungle clearing, with their roots on the bund and slopes and grip cutting.	Lump	sum
2	Earthwork to bund including watering and tamping, etc., complete.	C.yd.	3,550
3	Turfing the front and rear slopes of bund	Sqr.	270
4	Providing guage stones	No.	1
5	Providing Reg. No. and date stone	Each	1
6	Providing B. M. sluices	"	2
7	Grade stones including figuring and painting, etc., complete.	"	12
8	Index stones	"	12
	Sluice No. 1 at C. S. No. 5.		
1	Cut opening the bund-earthwork excavation for foundation.	C.yd.	22
2	Refilling with watering and tamping	"	17
3	Concrete in surki mortar	C.ft.	178
4	Size stone in surki mortar	"	285
5	Pointing in surki mortar	Sqr.	300
6	Stone slabs 6" thick dressed and put up	S.ft.	67
7	Making orifice	Lump	sum
8	C. I. pipes 7" dia. including carting to site and fixing with lead complete.	R.ft.	27
9	Providing teakwood rod with plug including locking arrangement.	Lump	sum
	Sluice No. 2 at C. S. No. 11.		
1	Cut opening the bund earthwork excavation for foundation.	C.yd.	6
2	Concrete in surki mortar	C ft.	151
3	Size stone in surki mortar	"	194
4	Burnt stone slabs 6" thick dressed and put up ...	S.ft.	60
5	Pointing with surki mortar	S.yd.	3
6	Making orifice holes in slabs	Lump	sum
7	C. I. pipes 7" dia. including carting to site and fixing, etc., complete.	R.ft.	27